

### Notes :

- (A) Control box mounted on the side of each TRU by the equipment manufacturer.
- (B) Not used.
- (C) Primary power by Division 16 electrical contractor.
- (D) Transformer panel and secondary power by ATC. Note : location and number of panels and transformers shall be determined by the ATC Contractor.
- (E) Damper Actuator and TEC by ATC Contractor.
- (F) Electronic Room Sensor and wall box by ATC. Mounting height - 60" AFF.
- (G) Electronic Reheat Valve furnished by ATC and installed in piping system by Mechanical Contractor.
- (H) Not used.


- (I) At each control box provide a toggle type switch (TS) suitable for 24 VAC mounted in a junction box on the side of each control box.
- (J) 2-#14 AWG stranded wires (24 VAC) in 3/4" EMT daisy chain between each TRU by ATC.
- (K) 1-#20 TSP cable in 3/4" EMT to field panel by ATC.
- (L) Pre-terminated cable (6 wire) in 1/2" EMT between Room Sensor and TEC by ATC. See Note 'F' for rough in mounting height of Room Sensor.
- (M) 3-#14 AWG stranded wires between TEC and Reheat Valve by ATC.
- (N) Not Used.
- (O) Not Used.
- (P) Supply Air Temperature Sensor furnished and installed by ATC.
- (Q) Disconnect switch by ATC.

### Legend :

- ATC Automatic Temperature Controls
  - TEC Terminal Equipment Controller
  - TSP Twisted Stranded Pair
  - DA Damper Actuator
  - DS Disconnect Switch
  - JB Junction Box
  - T Transformer
  - TS Toggle Type Disconnect Switch
  - TRU Terminal Reheat Unit
  - SA Supply Air
- \* This equipment can be either field installed by ATC or shipped to TRU manufacturer by ATC for factory mounting by equipment manufacturer.

## Direct Digital Control (DDC) Typical BAS Wiring Diagram - TRU

No Scale



## Notes :

- (A) Control box mounted on the side of each TRU by the equipment manufacturer.
- (B) Control box and retrofit kit for each existing TRU. See specifications for additional information.
- (C) Primary power by Division 16 electrical contractor.
- (D) Transformer panel and secondary power by ATC. Note : location and number of panels and transformers shall be determined by the ATC Contractor.
- (E) Damper Actuator and TEC by ATC Contractor.
- (F) Electronic Room Sensor and wall box by ATC. Mounting height - 60" AFF.
- (G) Electronic Reheat Valve furnished by ATC and installed in piping system by Mechanical Contractor.
- (H) Existing Pneumatic Reheat Valve to be reused. See specifications for additional information.
- (I) At each control box provide a toggle type switch (TS) suitable for 24 VAC mounted in a junction box on the side of each control box.
- (J) 2-#14 AWG stranded wires (24 VAC) in 3/4" EMT daisy chain between each TRU by ATC.
- (K) 1-#20 TSP cable in 3/4" EMT to field panel by ATC.
- (L) Pre-terminated cable (6 wire) in 1/2" EMT between Room Sensor and TEC by ATC. See Note 'F' for rough in mounting height of Room Sensor.
- (M) 3-#14 AWG stranded wires between TEC and Reheat Valve by ATC.
- (N) Pneumatic Transducer with air line to existing valve and TEC by ATC.
- (O) Pneumatic air supply to Transducer by ATC.
- (P) Supply Air Temperature Sensor furnished and installed by ATC.
- (Q) Disconnect switch by ATC.


## Legend :

- |   |                                |
|---|--------------------------------|
| ATC   | Automatic Temperature Controls |
| * TEC   | Terminal Equipment Controller  |
| TSP   | Twisted Stranded Pair          |
| * DA  | Damper Actuator                |
| DS  | Disconnect Switch              |
| JB  | Junction Box                   |
| T   | Transformer                    |
| * PT  | Pneumatic Transducer           |
| * TS  | Toggle Type Disconnect Switch  |
| TRU   | Terminal Reheat Unit           |
| SA  | Supply Air                     |
| * This equipment can be either field installed by ATC or shipped to TRU manufacturer by ATC for factory mounting by equipment manufacturer. |                                |

## DDC & Pneumatic Controls

# Typical BAS Wiring Diagram - TRU

No Scale



**Notes :**

- (A) Control box mounted on the side of each TRU by the equipment manufacturer.
- (B) Control box mounted on the side of each ETU by the equipment manufacturer.
- (C) Primary power by Division 16 electrical contractor.
- (D) Transformer panel and secondary power by ATC. Note : location and number of panels and transformers shall be determined by the ATC Contractor.
- (E) Damper Actuator and/or TEC by ATC Contractor.
- (F) Electronic Room Sensor and wall box by ATC. Mounting height - 60" AFF.
- (G) Electronic Reheat Valve furnished by ATC and installed in piping system by Mechanical Contractor.
- (H) Existing Pneumatic Reheat Valve to be reused. See specifications for additional information.

- (I) At each control box provide a toggle type switch (TS) suitable for 24 VAC mounted in a junction box on the side of each control box.
- (J) 2-#14 AWG stranded wires (24 VAC) in 3/4" EMT daisy chain between each TRU by ATC.
- (K) 1-#20 TSP cable in 3/4" EMT to field panel by ATC.
- (L) Pre-terminated cable (6 wire) in 1/2" EMT between Room Sensor and TEC by ATC. See Note 'F' for rough in mounting height of Room Sensor.
- (M) 3-#14 AWG stranded wires between TEC and Reheat Valve by ATC.
- (N) Pneumatic Transducer with air line to the TEC by ATC.
- (O) Pneumatic air supply to Transducer by ATC.
- (P) Supply Air Temperature Sensor furnished and installed by ATC.
- (Q) Disconnect switch by ATC.


**Legend :**

- ATC Automatic Temperature Controls
  - \* TEC Terminal Equipment Controller
  - TSP Twisted Stranded Pair
  - \* DA Damper Actuator
  - DS Disconnect Switch
  - JB Junction Box
  - T Transformer
  - VS Velocity Sensor
  - TRU Terminal Reheat Unit
  - ETU Exhaust Terminal Unit
  - LFH Laboratory Fume Hood
  - \* PT Pneumatic Transducer
  - \* TS Toggle Type Disconnect Switch
  - SA Supply Air
- \* This equipment can be either field installed by ATC or shipped to TRU manufacturer by ATC for factory mounting by equipment manufacturer.

**DDC & Pneumatic Controls**

**Typical BAS Wiring Diagram - TRU, ETU & LFH**

No Scale



### Notes :

- (A) Control box mounted on the side of each TRU by the equipment manufacturer.
- (B) Control box mounted on the side of each ETU by the equipment manufacturer.
- (C) Primary power by Division 16 electrical contractor.
- (D) Transformer panel and secondary power by ATC. Note : location and number of panels and transformers shall be determined by the ATC Contractor.
- (E) Damper Actuator and/or TEC by ATC Contractor.
- (F) Electronic Room Sensor and wall box by ATC. Mounting height - 60" AFF.
- (G) Electronic Reheat Valve furnished by ATC and installed in piping system by Mechanical Contractor.
- (H) Not Used.

- (I) At each control box provide a toggle type switch (TS) suitable for 24 VAC mounted in a junction box on the side of each control box.
- (J) 2-#14 AWG stranded wires (24 VAC) in 3/4" EMT daisy chain between each TRU by ATC.
- (K) 1-#20 TSP cable in 3/4" EMT to field panel by ATC.
- (L) Pre-terminated cable (6 wire) in 1/2" EMT between Room Sensor and TEC by ATC. See Note 'F' for rough in mounting height of Room Sensor.
- (M) 3-#14 AWG stranded wires between TEC and Reheat Valve by ATC.
- (N) Not Used.
- (O) Not Used.
- (P) Supply Air Temperature Sensor furnished and installed by ATC.
- (Q) Disconnect switch by ATC.


### Legend :

- ATC Automatic Temperature Controls
  - \* TEC Terminal Equipment Controller
  - TSP Twisted Stranded Pair
  - \* DA Damper Actuator
  - DS Disconnect Switch
  - JB Junction Box
  - T Transformer
  - VS Velocity Sensor
  - TRU Terminal Reheat Unit
  - ETU Exhaust Terminal Unit
  - LFH Laboratory Fume Hood
  - \* PT Not Used
  - \* TS Toggle Type Disconnect Switch
  - SA Supply Air
- \* This equipment can be either field installed by ATC or shipped to TRU manufacturer by ATC for factory mounting by equipment manufacturer.

### DDC Controls

## Typical BAS Wiring Diagram - TRU, ETU & LFH

No Scale



Notes :

- (A) Control box mounted on the side of each TRU by the equipment manufacturer.
- (B) Control box mounted on the side of each ETU by the equipment manufacturer.
- (C) Primary power by Division 16 electrical contractor.
- (D) Transformer panel and secondary power by ATC. Note : location and number of panels and transformers shall be determined by the ATC Contractor.
- (E) Damper Actuator and/or TEC by ATC Contractor.
- (F) Electronic Room Sensor and wall box by ATC. Mounting height - 60" AFF.
- (G) Electronic Reheat Valve furnished by ATC and installed in piping system by Mechanical Contractor.
- (H) Not Used.
- (I) At each control box provide a toggle type switch (TS) suitable for 24 VAC mounted in a junction box on the side of each control box.
- (J) daisy chain between each TRU by ATC.
- (K) 1-#20 TSP cable in 3/4" EMT to field panel by ATC.
- (L) Pre-terminated cable (6 wire) in 1/2" EMT between Room Sensor and TEC by ATC. See Note 'F' for rough in mounting height of Room Sensor.
- (M) 3-#14 AWG stranded wires between TEC and Reheat Valve by ATC.
- (N) Not Used.
- (O) Not Used.
- (P) Supply Air Temperature Sensor furnished and installed by ATC.
- (Q) Disconnect switch by ATC.

Legend :

- ATC Automatic Temperature Controls
  - TEC Terminal Equipment Controller
  - TSP Twisted Stranded Pair
  - DA Damper Actuator
  - DS Disconnect Switch
  - JB Junction Box
  - T Transformer
  - VS Velocity Sensor
  - TRU Terminal Reheat Unit
  - ETU Exhaust Terminal Unit
  - LFH Laboratory Fume Hood
  - PT Not Used
  - TS Toggle Type Disconnect Switch
  - SA Supply Air
- \* This equipment can be either field installed by ATC or shipped to TRU manufacturer by ATC for factory mounting by equipment manufacturer.

DDC Controls

Typical BAS Wiring Diagram - TRU & ETU

No Scale